






GENERAL SPECIFICATIONS	TYPE	BRAILLE CELL	BRAILLE DOT	MOUNTING LOCATION
<p>Typestyle: San Serif Typestyles only</p> <p>Width to Height Ratio: 3:5-1:1 or 60%-100% <b>A</b></p> <p>Stroke to Height Ratio: 1:5-1:10 or 10%-20% <b>B</b></p> <p>Type Size: 5/8" Min.- 2" Max. based on capital "I"</p> <p>Line Spacing: 135%-170%</p> <p>Letter Spacing: 1/8" min.- 3/8" max.</p> <p>Braille Size: See Example <b>C</b></p> <p>Braille Location: Located directly below tactile lettering with a min. 1/4"</p> <p>Mounting Location: Min. 3" from door swing, 60" on center. <b>D</b></p>	<p>Width to Height Ratio: 3:5-1:1 or 60%-100%</p>  <p><b>A</b></p> <p>Stroke to Height Ratio: 1:5-1:10 or 10%-20%</p>  <p><b>B</b></p>	<p>FED. INTER-CELL SPACING=.241"-.30" CA. INTER-CELL SPACING=.30"</p>  <p>FED. INTER-CELL SPACING = .09"-.10" CA. INTER-DOT SPACING = .10"</p> <p><b>C</b></p> <p>SCALE: FULL SIZE</p>	<p>DOT HEIGHT=.025"-.037"</p>  <p>DOT DIAMETER=.059"-.063"</p> <p><b>D</b></p> <p>SCALE: 4:1</p>	<p>MIN. 3"</p>  <p>60" O.C.</p> <p>SCALE: 1/4"=1'-0"</p>

ELEVATION & SIDE

Letter Spacing: 1/8" Min.-Max. 3/8"(Min. Shown in White)

MAXIMUM LETTER SPACING (3/8") SHOWN IN GREEN

Note: Spacing is determined at top of bevel or dome.


Type Size: 5/8" Min.- 2" Max. based on capital "I" (Min. Shown)

Line Spacing 135%-170% of Letter Height (Min. Shown in White)

MAXIMUM LINE SPACING SHOWN IN RED

Braille:24 pt. Grade 2 Braille, round or domed shape dots. Dot size and spacing as per ADAAG, ANSI or state specification. (In California only Ca. Grade 2 Braille allowed) located below tactile (visual) letters a min. of 1/4".

TYPE IN ALL LOWER CASE




ELEVATION

SCALE 1:2

Non-glare finish with 70% contrast between field color and visual text.

Keep raised decorative elements at least 3/8" away from tactile lettering and braille. Glare producing materials should be placed away from information.



SIDE

SCALE 1:2